

Type Mark	Description	Manufacturer	Model	Count
E	Light Pole	Watts	Chart Series New LED Symmetric	5


- General Notes:**
- This drawing is to be read in conjunction with all relevant Architect's and Structural Engineer's Construction Method Drawings, Fire Certificate and Fire Drawings, along with the contractors Mechanical and Electrical specifications and any other documentation.
 - Do not cover over the drawings.
 - The drawing is representative only. All dimensions are in millimeters (mm), unless otherwise stated. Use the typical dimensions where shown.
 - The exact location of all services and fittings to be agreed on site with the Architect and/or Structural Engineer prior to their installation.
 - The Mechanical and Electrical Services are to be coordinated with all other trades and to be agreed on site prior to their installation. The contractor shall allow for the setting out and installation around all obstructions. Additional costs incurred by the contractor due to the lack of coordination will not be reimbursed.
 - Connections to all equipment to be made by the contractor.
 - Any discrepancy between this drawing and on site conditions must be reported to Renaissance Engineering LTD. immediately. Any changes from this design drawing must be agreed with the Engineer in writing. A failure to gain this approval could lead to difficulty in approving payment for the installation.
 - Installation / Construction / As-Built Drawings to be prepared by the Mechanical/Electrical Contractor with reference to the latest Architect's and Structural Engineer's construction issue drawings and fire certificate drawings.
 - All Electrical works to comply with the National Rules for Electrical Installations, 5th Edition IS 6392:2005.
 - All Mechanical and Electrical works to comply with the current Building Regulations.

- Lighting Services Notes:**
- Lighting Wiring 2.5mm² PVC cable including earth, loop in method, no joints allowed. Protection 10A MCB Type B RC 32T1.
 - Exact position of light fittings to be agreed on site in consultation with the Architect and/or Engineer.
 - External lighting wiring minimum 2.5mm² PVC cable. External lighting controlled by photocell.
 - All luminaires shall be subject to approval by the Client's Design Team. The Specialist shall allow for a cost and the relevant construction programme requirements for each type of luminaire specified herein.
 - All secondary containment wiring the lighting shall be designed, supplied and installed by the Specialist Contractor. The secondary containment shall be supplied and installed as per the specification and schedules.
 - The exact mounting height and location of luminaires shall be agreed on site with the Engineer and Architect prior to installation.
 - The electrical contractor shall include for the supply, installation, test and commissioning of the entire lighting control system, including final testing and the commissioning of same.
 - Final selection of luminaires shall be agreed with the Client during construction, prior to order.
 - Light switching / control devices shall generally be as per the drawings. The final position of the light switches / control devices shall be agreed with the engineer prior to installation.
 - Lighting control circuits shall be protected by a 10A Type B RCBO (equal to existing) and general lighting circuits (luminaires only) shall be protected by a 10A Type B RCBO.
 - All luminaires shall be as per the Architect's finishes schedule.
 - All luminaires to be supplied with lamps, control gear, supports and ancillaries to complete the installation to the manufacturer's recommendations.

- Emergency Lighting Services Notes:**
- Emergency lighting wiring 2.5mm² PVC cable in trunking and conduit controlled by proprietary emergency lighting test facility.
 - Emergency lighting installation to comply with I.S. 3217:2002+A1:2017 (or current edition).
 - The contractor / Specialist shall supply, install, inspect, verify, test and commission a complete emergency lighting installation alignment with the requirements of I.S. 3217:2002+A1:2017 (or current edition).
 - All emergency lighting equipment shall be supplied from a single vendor / supplier / manufacturer.
 - The specialist shall provide complete certification for inclusion in the building safety file and O&M manual in alignment with the requirements of I.S. 3217:2002+A1:2017 (or current edition).
 - All equipment shall be supplied as per the drawings, specifications and schedules.
 - A Sample of each item of equipment shall be provided to the Architect and Engineer for inspection for sign off / approval prior to the commencement of final fit installation works.

Legend

⊙ Light Pole



Revision Table:

Rev	Date	Revision Description	Rev	CHK
P01	2025/11/07	Lighting Updated	R.S.	B.S.
P	2025/03/21	Initial Issue	A.B.	B.S.

Company Logo: Renaissance Engineering
 Address: 2nd Floor, 61-75 South Street, Dublin 8, D08 Y0K4, Ireland
 Telephone: +353 (0) 1 751 8800
 Email: info@reng.ie
 Web: www.reng.ie

Client: Midcal Homes Limited
 Architect: Donnelly-Turpin Architects
 Project Name: Belgard Apartments
 Belgard Road Mixed Use Development, Tallaght, Dublin 24

Sheet Name: Lighting Services
 First Floor
 Site

Scale: As Indicated @ A0
 Document Number: 24242-REN-XX-01-DR-E-6300
 Revision: P01
 Approved By: [Signature]
 Draft Filename: 24242-REN-22-22-M5-ME-001.rvt
 Internal Project Number: 24-242