

- SEPARATION DISTANCES BETWEEN WATERMANS ASSOCIATED WITH THE WORKS FROM OTHER UTILITY PIPES AND ACCESSORIES SHALL BE IN ACCORDANCE WITH SECTION 3.6 OF THE CODE OF PRACTICE. SEPARATION DISTANCES FOR ALL NEW INSTALLATIONS FROM EXISTING IRISH WATER PIPES SHALL BE AS OUTLINED IN SECTION 3.27 OF THE CODE OF PRACTICE. THE SEPARATION DISTANCES SPECIFIED ARE MINIMUM DISTANCES.
- SPECIFIC SEPARATION CLEARANCE DISTANCES IN EXCESS OF THESE MINIMA SHALL BE PROVIDED FOR SERVICES SUCH AS GAS, ELECTRICITY, FIBRE-OPTIC OR OIL FILLED CABLES AS THE CASE MAY BE. THE PARTICULAR UTILITY PROVIDERS SHALL BE CONSULTED TO DETERMINE THESE MINIMUM SEPARATION DISTANCES AND EVIDENCE OF THIS CONSULTATION, WITH THE SPECIFIED SEPARATION DISTANCES, SHALL BE PROVIDED TO IRISH WATER AT DESIGN STAGE.
- WATERMAIN (PROPOSED) SEPARATION DISTANCES**  
**HORIZONTAL**  
 300mm TO DISTRIBUTION MAINS OF LESS THAN 300mm DIAMETER.  
 500mm TO TRUNK MAINS BETWEEN 300mm AND 450mm DIAMETER.  
 3m TO ARTERIAL WATER MAINS OF GREATER THAN 450mm DIAMETER.  
**VERTICAL**  
 300mm TO DISTRIBUTION MAINS OF LESS THAN 300mm DIAMETER.  
 500mm TO TRUNK/ARTERIAL MAINS OF DIAMETER GREATER THAN 300mm.

ANY PROPOSED PIPE CROSSING SHOULD BE LOCATED MID-WAY BETWEEN THE WATER JOINTS WITH MINIMUM CLEAR DISTANCE OF 300mm AND UP TO 500mm.  
 ALL CROSSINGS SHOULD BE AT LEAST 500mm AWAY FROM FITTINGS OR JOINTS


- WATERMAIN (EXISTING) SEPARATION DISTANCES**  
**HORIZONTAL**  
 IN THE CASE OF INSTALLATIONS IN CLOSE PROXIMITY TO EXISTING WATER MAINS AND SEWERS, THE FOLLOWING MINIMUM HORIZONTAL DISTANCES SHALL BE MAINTAINED BETWEEN PIPES/DUCTS, CABINETS, POLES, MANHOLES, JUNCTION BOXES, CHAMBERS, ETC.  
 WHERE THE DEPTH OF THE EXISTING INFRASTRUCTURE DOES NOT EXCEED 1.5m  
 600mm AT EITHER SIDE OF MAINS UP TO AND INCLUDING 150mm DIAMETER;  
 1m AT EITHER SIDE OF MAINS OF 200mm TO 250mm DIAMETER; 2m AT EITHER SIDE OF MAINS OF 300mm AND 375mm DIAMETER; 5m AT EITHER SIDE OF MAINS OF 400mm AND 450mm DIAMETER;  
 SPECIFIC IRISH WATER ADVISED DISTANCES FOR MAINS IN EXCESS OF 450mm;  
 600mm AT EITHER SIDE OF GRAVITY SEWER UP TO AND INCLUDING 225mm DIAMETER;  
 1m AT EITHER SIDE OF GRAVITY SEWER OF 300mm AND UP TO 450mm DIAMETER;  
 1.5m AT EITHER SIDE OF GRAVITY SEWERS OF 600mm DIAMETER AND GREATER ;  
 5. NOTIFICATION IN WRITING IS REQUIRED SHOULD WORKS BE WITHIN THE FOLLOWING DISTANCES FROM AN EXISTING WATER MAIN OR WASTEWATER RISING MAIN WHERE THE DEPTH OF THE EXISTING INFRASTRUCTURE DOES NOT EXCEED 1.5m-  
**HORIZONTAL**  
 1m AT EITHER SIDE OF EXISTING PIPES LESS THAN 200mm DIAMETER;  
 2m AT EITHER SIDE OF EXISTING PIPES OF 200mm TO 350mm DIAMETER;  
 5m AT EITHER SIDE OF EXISTING PIPES OF 350mm OR GREATER;

SPECIFIC WRITTEN APPROVAL WILL BE REQUIRED FROM IRISH WATER BEFORE PROCEEDING WITH THE WORK  
 NOTIFICATION IN WRITING IS REQUIRED SHOULD WORKS BE WITHIN 1.5m DISTANCE OF A WASTEWATER SEWER.

REQUIREMENTS SHALL ALSO APPLY TO TRIAL HOLES OR SLIT TRENCHES TO LOCATE THE MAIN OR GAIN GROUND INFO DATA.  
 LARGER DIAMETERS >300mm DISTRIBUTION AND TRUNK MAINS, IRISH WATER MUST BE NOTIFIED AT LEAST 1 MONTH IN ADVANCE.

DEVELOPERS SHALL ALSO COMPLY WITH ANY NOTIFICATION REQUIREMENTS OF OTHER UTILITY PROVIDERS (ESB, GAS MAIN, TELECOMMUNICATION ETC).

- DETAILED PROPOSALS, INCLUDING WORK METHOD STATEMENTS, INSURANCE CONFIRMATION AND DETAILS OF WORK COMPLETED OF A SIMILAR NATURE MUST BE SUBMITTED TO IRISH WATER FOR ITS CONSIDERATION BEFORE AGREEMENT WILL ISSUE. ALL SUCH WORKS IN THE VICINITY OF ARTERIAL WATER MAINS AND SEWERS (MAINS GREATER THAN 400mm) SHALL BE SUBJECT TO WRITTEN AGREEMENT WITH IRISH WATER BEFORE CONSTRUCTION COMMENCES ON SITE. THIS AGREEMENT SHALL ALSO INCLUDE ANY NECESSARY PROTECTION FOR WATER MAINS.
- ANY DAMAGE SHALL BE NOTIFIED IMMEDIATELY TO IRISH WATER. THE PERSON WHO CAUSES THE DAMAGE TO A WATER MAIN OR FITTING WILL BE DEEMED TO HAVE COMMITTED AN OFFENCE UNDER SECTION 45 OF THE WATER SERVICES ACT 2007.
- WATERMANS OF ANY SIZE SHALL NOT BE WITHIN 1m OF THE BOUNDARY TO A PREMISES.
- UNDER NO CIRCUMSTANCES WILL IRISH WATER ACCEPT WATER MAIN INSTALLATIONS UNDER STRUCTURES, EXISTING OR PROPOSED, OR IN CLOSE PROXIMITY TO ANY EXISTING STRUCTURES OR FEATURES THAT WILL INHIBIT ACCESS FOR POST INSTALLATION MAINTENANCE AND ACCESS.
- WHERE THE DESIGN DEVIATES FROM THIS STANDARD DETAIL, THE DESIGN SHALL BE SUBJECT TO THE REVIEW OF IRISH WATER.
- SEPARATION DISTANCES BETWEEN UTILITIES MAY BE INCREASED TO PROVIDE FOR CHAMBER & THRUST BLOCKS AT BENDS.
- WHERE A GRASS VERGE IS NOT AVAILABLE AND A FOOTPATH IS LESS THAN 1.5m WIDE, THE WATERMAIN IS PERMITTED ON THE ROADWAY.



**STD-W-11 TYPICAL SERVICE LAYOUT INDICATING SEPARATION DISTANCES**  
 NTS

**METHOD STATEMENTS:**  
 ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH BS 5837 AND INFORMED BY NUJG VOLUME 4


**PRECAUTION AREA:**  
 EXCAVATIONS FOR PIPEWORK SHOULD NOT BE UNDERTAKEN WITHIN THIS AREA, UNLESS AGREED WITH IRISH WATER.

WORKS WITHIN THE PRECAUTION ZONE MUST BE SUPERVISED BY A QUALIFIED ARBORIST. WORKS SHALL BE SUBJECT OF A CLEAR METHOD STATEMENT OUTLINING ALL WORKS ADJACENT TO THE TREES/SHRUBS WHICH IS TO BE PREPARED AND AGREED IN ADVANCE OF THE WORKS.


MATERIAL, PLANT AND SPOIL SHALL NOT BE STORED WITHIN THIS ZONE.

**EXCLUSION AREA:**  
 WORKS IN THIS AREA ARE TO BE AVOIDED, UNLESS ABSOLUTELY NECESSARY AND AGREED WITH IRISH WATER.

EXCAVATIONS FOR PIPEWORK SHOULD NOT BE UNDERTAKEN WITHIN THIS AREA, UNLESS NECESSARY AND NO OTHER OPTIONS AVAILABLE. WORKS WITHIN THE EXCLUSION ZONE MUST BE SUPERVISED BY A QUALIFIED ARBORIST AND AGREED WITH IRISH WATER. WORKS SHALL BE SUBJECT OF AN ARBORICULTURAL IMPACT ASSESSMENT AS PER BS 5837 AND A CLEAR METHOD STATEMENT OUTLINING ALL WORKS ADJACENT TO THE TREE/SHRUBS IS TO BE PREPARED AND AGREED IN ADVANCE OF THE WORKS. MATERIAL, PLANT AND SPOIL SHALL NOT BE STORED WITHIN THIS ZONE.



PREVENTION MEASURES REQUIRED IN LINE WITH LANDSCAPING DESIGN AND SPECIAL PROTECTION REQUIRED (E.G. BY USE OF APPROPRIATE BARRIERS, HIGH PERFORMANCE JOINTS, OR BY USE OF POLYETHYLENE WITH WELDED JOINTS). THE LANDSCAPE DESIGN AND DETAILS OF THE SPECIAL PROTECTION MEASURES MUST BE AGREED WITH IRISH WATER



**EXISTING PLANTING:**

**STD-W-12 RESTRICTIONS ON WATER INFRASTRUCTURE WORKS ADJACENT TO EXISTING TREES**  
 NTS

**Notes:**  
 For setting out refer to Architect's drawings.  
 This drawing shall be read in conjunction with all other Architectural and Engineering drawings and all other relevant drawings and Specifications.  
 DO NOT SCALE FROM THIS DRAWING. Use figured dimensions only.  
 Verify dimensions on site and report any discrepancies to the author immediately.  
 This drawing is copyright © and must not be reproduced, transmitted or stored in any form without the written permission of Torque Consulting Engineers Limited except as agreed for use on the project for which the document was originally issued.

PO1	EK	JdP	ISSUED FOR INFORMATION	17/10/2025
Rev	Drn	Chkd	Amendments	Date

Rev	Drn	Chkd	Amendments	Date
-----	-----	------	------------	------

FOR PLANNING

Drawing Sheet Size: A1

Architect: DONNELLY TURPIN ARCHITECTS			
Project: MIXED USE DEVELOPMENT BELGARD SQ. EAST, BELGARD RD, TALLAGHT			
Title: WATER MAIN DETAILS SHEET 01 OF 05			
Drg No: S058-TCE-B1-ZZ-DR-S-S-621	Revision: P01		
Scale: NTS	Date: 17/10/2025	Status: PLANNING	
Drn By: EK	Chkd By: JdP	Aprvd By: JdP	

**TORQUE**  
 CONSULTING ENGINEERS  
 CIVIL & STRUCTURAL

Unit K26,  
 Drinan Enterprise Centre,  
 Swords Enterprise Park,  
 Swords,  
 K67 E722  
 Ireland

T: +353 (0)1 4853933  
 E: contactus@tce.ie  
 W: www.tce.ie